



CDBG-DR 13 CHANGE ORDER OR WORK ORDER AMENDMENT



Project Information

Project Name	Eagle Dr.				
Work Order Number (CDBG-DR 01)	I-19-W-URG	Project Address	Eagle Dr. from SW 19 th to SW 14th		
Date	3/29/2017	Requested By	Rudy Construction		
Date Requested	3/24/2017	Total Budget	\$723,658.84	Cost of Change	\$18,052.69

Change Order Type - Description

Circle Type:	Field	Change	Work Order Amendment	
Budget Line Items Affected: (List All)				
200-00	Unclassified Excavation (>500 CY)	15.00CY	Quantity: 734.13	Total: \$11,011.95
213-03	Crushed Rock Foundation	70.00CY	Quantity: 858.72	Total: \$60,110.40
304-04	Portland Cement Concrete Pavement	55.00CY	Quantity: 3,927.10	Total: \$215,990.50
305-05	Curb & Gutter (2'-8")(6" Barrier)	20.00LF	Quantity: 3,480.30	Total: \$69,606.00
812-02	Remove Curb & Gutter	7.00LF	Quantity: 3,480.30	Total: \$24,362.10
812-03	Concrete Pavement Removal	10.00SY	Quantity: 3,927.10	Total: \$39,271.00
813-00	Remove Driveway	10.00SY	Quantity: 959.08	Total: \$9,590.80
820-01	Sawcut Pavement	4.00LF	Quantity: 1,362.83	Total: \$5,451.32
812-01	Remove Sidewalk	10.00SY	Quantity: 768.89	Total: \$7,688.90
823-00	Sidewalk (5')	55.00SY	Quantity: 1,391.44	Total: \$76,529.20
823-03	6" PC Conc. Driveway (HES)	65.00SY	Quantity: 1,037.42	Total: \$67,432.30
824-01	Temporary Surface Course (TBSC)	40.00Ton	Quantity: 288.28	Total: \$11,531.20

840-04 Solid Slab Sodding (U-3 Bermuda)	3.00SY	Quantity: 1,050.00	Total: \$3,150.00
740-09 Construction Barricades	10.00SD	Quantity: 236.00	Total: \$2,360.00
740-10 Warning Lights (Type A)	1.00SD	Quantity: 506.00	Total: \$506.00
740-14 Channelizer Cones	1.50SD	Quantity: 5,208.00	Total: \$7,812.00
740-03 Construction Sign (0-6.25sf)	1.00 SD	Quantity: 926.00	Total: \$926.00
740-04 Construction Sign (6.26-15.99sf)	2.00 SD	Quantity: 176.00	Total: \$352.00
740-05 Construction Sign (16-32.99sf)	5.00 SD	Quantity: 201.00	Total: \$1,005.00
840-04 Tactile Markers/Truncated Domes	25.00 SF	Quantity: 21	Total: \$525.00

Mobilization Increase of \$1,181.02

Change Description	813-00: Driveway removal ran over per City instructions. Originally removing only 3' of driveway approach. Rudy was instructed to take the removal and replacement all the way back to the property line to accommodate ADA requirements.
	820-01: Original estimate was for transverse cuts only to accommodate daily concrete pours. Actual construction required longitudinal sawing to allow for setting of forms rather than to pour against the old broken existing concrete down the centerline of the street.
	812-01: Extra sidewalk removed to accommodate the entry feature at 19 th St. The sidewalk was not included in the original quantity.
	823-00: Original estimate placed sidewalk on one side of Eagle Dr only. The City decided to place sidewalk on both sides of Eagle in between 19 th & 14 th Street.
	823-03: See item 813-00. Replaced driveways removed. Also added width to several driveways and added three driveways that weren't on the original takeoff. Per inspector.
	824-01: Original quantity was for one temporary install and removal at each driveway. Actual construction required multiple movements of temporary driveway access to accommodate residents.
	740-03, 04, 05, 14: Additional sizes and kinds of traffic signs were needed to meet traffic safety requirements.
459-01 & 460-01: A new manhole ring and cover was needed to bring the existing manhole to code. The existing manhole needed to be adjusted to the new grade required by the new entry feature.	

Field Change Order			
Field Change Order Authorization ONLY		Date	
Vendor Signature			