

CITY OF MOORE
KELLY CREEK DRAINAGE REPLACEMENT
BID # 2021-010
Request For Information #3

Date: 4/2/2021

1. Is the intent to use the utility easement for work access from station 63+60 to 71+00 where no temporary construction easement is shown?
 - a. Yes
2. Are we allowed to use utility easements for access on both sides of the channel, since fence is being replaced in most locations?
 - a. Yes
3. Can we use the utility easement that are located between houses?
 - a. No
4. Are structures, sheds, etc., that are in the utility and temporary easement to be removed by landowner or contractor? Who is responsible to replace structures that are removed?
 - a. Refer to Construction Notes on Sheets 28 through 36. The Contractor is responsible for addressing the structures as indicated on the plans.
5. Can a filter fabric that meets the project requirements be specified or approved equal?
 - a. Refer Plan Sheet 5, Note 10.
 - b. Refer to the ODOT latest edition Standard Specifications for Highway Construction. Provide a fabric that meets the requirements of the specification as described in section 712.02, Geotextiles for Erosion Control in accordance with AASHTO M 288, "Permanent Erosion Control Geotextile Requirements."
6. Does the sanitary sewer at station 48+40 have a steel casing to protect it during construction of the channel?
 - a. No.
7. Sheet 9, RCB quantities for the steel and class A, is this for each end section?
 - a. The Total Quantity columns for Reinforcing Steel (LBS.) and Concrete (C.Y.) are for one headwall.
8. Sheet 10, Typical Expansion Joint, is this for the floor and sloped walls both?
 - a. Yes, it is for the floor and sloped walls. The pedestal is to be placed on the channel bottom only.
9. Sheets 13 and 14, is all the shaded areas from the back of the curb to the concrete channel and wing walls class C concrete?
 - a. Yes

CITY OF MOORE
KELLY CREEK DRAINAGE REPLACEMENT
BID # 2021-010
Request For Information #3

10. Do joints in the sloped walls of the channel get sealed also?
 - a. Yes

11. Does the class A concrete pay item quantity include the material for the 6" Dowel Jointed concrete pavement as per ODOT specifications?
 - a. Yes.

12. Is the concrete pedestal under the expansion joints included in the class A pay quantities?
 - a. Yes