



**NOTICE TO PROCEED**

**DATE:** May 25, 2021  
**TO:** Veolia  
**PROJECT:** Plaza Towers Water-Line Replacement

The City of Moore has considered the budget submitted by you for the above referenced project.

You are hereby notified the budget has been accepted in the amount of \$180,407.00.

The project will be completed by December 31, 2021.

You are required to return an acknowledged copy of Notice to Proceed to the City of Moore.

Dated this 25<sup>th</sup> day of May 2021.

By: Kahley Gilbert  
Kahley Gilbert, Project-Grants Manager

**ACCEPTANCE OF NOTICE**

Receipt of the foregoing Notice to Proceed is hereby acknowledge by M Pistole  
this 3 day of June, 2021.

By: Robert Pistole

Title: Project Manager



Quote

Date: 02/03/2021

Project: Water Line Replacement in Plaza Towers

Project Description: The work is generally described as follows – provide material, labor and equipment to replace 1400 LF of 6” water line, 2500 LF of 8” PVC water line, install 24 existing double services, 21 long double sets and 5 fire hydrants. The project will meet all city, state and HUD requirements.

Work Description	Units	Quantity	Unit Price	Subtotal
Trench Embedment & Backfill Material	Ton	750	\$17.00	\$12,750.00
6” PVC Water Line (C900) (DR18)	LF	1400	\$26.00	\$36,400.00
8” PVC Water Line (C900) (DR18)	LF	2500	\$27.00	\$67,500.00
Long Double Service	Each	21	\$650.00	\$13,650.00
6” x 1” Tapping Saddle & Short Double Services	Each	24	\$275.00	\$6,600.00
6” 22.5 Ell (MJ Type)	Each	3	\$275.00	\$825.00
6” 45 Ell (MJ Type)	Each	2	\$275.00	\$550.00
6” Cap (MJ Type)	Each	6	\$275.00	\$1,650.00
12” x 8” Tee	Each	1	\$350.00	\$350.00
8” x 6” Tee	Each	2	\$350.00	\$700.00
6” x 6” Tee	Each	2	\$350.00	\$700.00
8” x 6” Reducer	Each	1	\$275.00	275.00
Spoil Removal	Ton	750	\$9.50	\$7,125.00
6” Gate Valve w/ Box (MJ Type)	Each	9	\$840.00	\$7,560.00
8” Valve	Each	2	\$900.00	\$1,800.00
Fire Hydrant Assembly	Each	5	\$2,800.00	\$14,000.00
Pressure Test	Each	2	\$350.00	\$700.00
Disinfection Test	Each	2	\$350.00	\$700.00
Sod	SQ	11,100	\$.52	\$5,772.00
Mobilization/Demobilization	Each	1	\$800.00	\$800.00
<b>Total Estimated Construction Cost</b>	<b>****</b>	<b>*****</b>	<b>*****</b>	<b>\$180,407.00</b>

Robert Pistole, Project Manager  
 Veolia Water North America  
 4000 S. Service Road; Moore, Oklahoma 73160  
 Tel: 405-793-5080 \* Fax: 405-793-5094